



HV Test Equipment

DEHNcap/P Test Unit



Description:

For nominal voltages of 230 V / 50 Hz.

Test unit for carrying out function tests of DEHNcap/P voltage indicators or other HR indicators.

Optionally, an HR unit can be used for carrying out the test.

The test unit is operated by mains power and produces test voltages for HR systems.

Technical Data:

System	HR
Test voltage	90V
Socket spacing	19 mm
Nominal capacity	500 mW
Max short-circuit current at test sockets	appr. 20 μ A

CODE	TYPE	DIMENSIONS mm	WEIGHT g
767 110	HR	43 x 74.5 x 35	70